

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to roads and drains in Yelahanka old Town areas Gandhinagara SC-ST areas and surroundings areas in ward no: 01 Yelahanka Sub Division

[illegible]

SI No	Description of work	Measurement					Qty	Rate	Amount
		Unit	No.	L	B	D			
	Consider 30% Qty for Removing & Refixing						111.13		
	Basic rate								
	Area weightage 6%							105.00	
	Total							6.3	
3	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 & 136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80						111.13	111.30	12368.94
	Earthwork Excavation								
	New Drain								
	Sugappa layout								
	3rd cross	cum	1	39	0.75	0.8	23.4		
	Parallel Road to Railway Track	cum	1	60.00	0.90	0.90	48.6		
	1st C main	cum	1	45.00	0.90	0.90	36.45		
	2nd Main Road	cum	1	35.00	0.90	0.85	26.775		
	Main Road(SBI road)	cum	2	62.00	0.90	1.05	117.18		
	New Culvert								
	Sugappa layout								
	3rd cross	cum	1	7.1	2	1.1	15.62		
	3rd cross	cum	2	6.5	1.8	1.1	25.74		
	2nd cross	cum	2	9.00	1.80	1.1	35.64		
	1st cross road	cum	1	7.50	1.80	1.1	14.85		
		cum	1	8.50	1.80	1.1	16.83		
	Appayyanna Beedi	cum	1	6.00	1.80	1.1	11.88		
	1st C main	cum	1	8.30	1.35	1.10	12.3255		
	Desilting								
	Drain								
	Sugappa layout								
	3rd cross	cum	1	39	0.45	0.5	8.775		
	1st cross road	cum	2	199.00	0.45	0.50	89.55		
	Appayyanna Beedi	cum	2	90.00	0.45	0.50	40.5		
	Basic rate							130.00	
	Area weightage 6%							7.80	
	5Km lead & Lift= 57+(2*1.28*5)							69.80	
	Total						524.12	207.60	108806.38
4	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	RCC Drain								
	Sugappa layout								
	3rd cross	cum	1	39	0.75	0.15	4.3875		
	Parallel Road to Railway Track	cum	1	60.00	0.9	0.15	8.10		
	1st C main	cum	1	45.00	0.9	0.15	6.08		

[illegible]

[illegible]

- | | |
|---|---|
| 6 | KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2 |
|---|---|

For Drain	Cum				108.16		
	kg	Steel assumed 60Kg/Cum of			6489.45		
	tonne				6.49		
For Drain wall	Cum				33.33		
	kg	Steel assumed 60Kg/Cum of Concrete			1999.80		
	tonne				2.00		
For Culvert	Cum				37.84		
	kg	Steel assumed 90Kg/Cum of Concrete			3405.69		
	tonne				3.41		
Basic rate						68233	
Area weightage 6%						4093.98	
Total					11.89	72326.98	860325.09

- | | |
|---|--|
| 7 | Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,complete. (Data Rate) |
|---|--|

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
			From item No. 3				534.00		
	Provide 30 % Qnty new Precast slab for missing and Damaged	sqm					160.20		
	Cororation Bank Road	Sqm	1	57.00	0.90		51.30		
	2nd Main Road	Sqm	2	79.50	0.90		143.1		
	New Drain								
	Sugappa layout								
	3rd cross	sqm	1	39	0.75		29.25		
	Parallel Road to Railway Track	Sqm	1	60.00	0.90		54.00		
	1st C main	Sqm	1	45.00	0.90		40.5		
	2nd Main Road	Sqm	1	35.00	0.90		31.5		
	Main Road(SBI road)	Sqm	2	62.00	0.90		111.6		
	Data rate							2337.00	
	Total						621.45	2337.00	1452328.65
8	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of all materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge								
	Culvert cover Slab								
			From item No. 2				11.21		
	Provide30 % Qnty new Precast slab for missing and Damaged	sqm					3.36		
	New Cover Slab								
	Sugappa layout								
	3rd cross	sqm	1	7.1	2		14.2		
	3rd cross	sqm	2	6.5	1.8		23.4		
	2nd cross	sqm	2	9.00	1.80		32.4		
	1st cross road	sqm	1	7.50	1.80		13.5		
	1st cross road	sqm	1	8.50	1.80		15.3		
	Appayyanna Beedi	sqm	1	6.00	1.80		10.8		
	Data rate							5418.00	
	Total						112.96	5418.00	612025.41
9	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggretes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)								
	1st cross road(LHS &RHS)	Cum	2	199.00	0.40	0.15	23.88		
	Corporation Bank	cum	2	184.00	0.4	0.15	22.08		
	Main Road(SBI road)	cum	2	62.00	0.40	0.15	7.44		
	Basic rate							5422.00	
	Area weightage 6%							325.32	
	Total						53.40	5747.32	306906.89

SI No	Description of work	Mesurement					Qty	Rate	Amount
		Unit	No.	L	B	D			
10	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)								
	1st cross road(LHS & RHS)	Nos	2	199.00			398.00		
	Corporation Bank	Nos	2	184			368		
	Main Road(SBI road)	Nos	2	62.00			124		
	Total length						890.00		
	No of Kerb Stones			Total Length/0.45			1977.78		
	Sub Total						1977.78		
	Basic rate							408.00	
	Area weightage 6%							24.48	
	Total						1977.78	432.48	855349.33
11	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (Page No.180. Iitem no.24.1 of KPWD S.R Bangalore Circle 2018-2019)								
	1st cross road(LHS & RHS)	sqm	2	199.00	0.40		159.20		
	Corporation Bank	sqm	2	184.00	0.4		147.2		
	Main Road(SBI road)	sqm	2	62.00	0.4		49.6		
	Basic rate							80.00	
	Area weightage 6%							4.80	
	Total						356.00	84.80	30,188.80
12	KSRRB 300-46. Scarifying by mechanical means stone metal crust 50mm to 100mm thick with pick axes along with premix carpet / surface dressing and stacking of old serviceable materials including cost of all labour charges complete as per specifications. MORTH / Chapter 3.No. 19.52 page no.146								
	Parallel Road to Railway Track								
		Sqm	1	10	16.00		160.00		
		Sqm	1	8	10.00		80.00		
		Sqm	1	11.00	4.00		44.00		
	Basic rate							39.00	
	Area weightage 6%							2.34	
	Total						284.00	41.34	11740.56
13	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146,								
	MES School Road	Sqm	1	104	4		416		
	Parallel Road to Railway Track								
		Sqm	1	13	3.8		49.4		
		Sqm	1	15	10		150		
	Parallel Road to Railway Track	Sqm	1	37.00	4.60		170.2		
	Basic rate							39.00	
	Area weightage 6%							2.34	

Sl No	Description of work	Mesurement				Qty	Rate	Amount
		Unit	No.	L	B	D		
	Total						785.60	41.34
14	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occurring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)							
	Appayyanna Beedi	Sqm	1	90	4		351	
	MES School Road	Sqm	1	104	4		416	
	Parallel Road to Railway Track	Sqm						
		Sqm	1	10	16		160.00	
		Sqm	1	8	10		80.00	
		Sqm	1	11	4.00		44.00	
		Sqm	1	13	3.80		49.4	
		Sqm	1	15	10.00		150	
	Parallel Road to Railway Track	Sqm	1	37	4.60		170.2	
	Basic rate						6.00	
	Area weightage 6%						0.36	
	Total						1420.60	6.36
								9035.02
15	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202(P.No.140- I.No.18.47) & Pg No.136, Item No.17.4,17.1 (5km lead = 57+2*1.28X5)							
	Appayyanna Beedi	Cum	1	90	4	0.2	70.2	
	Basic rate						899.00	
	Area weightage 6%						53.94	
	5Km lead & Lift= 57+(2*1.28*5)						69.80	
	Total						70.20	1022.74
								71796.35
16	KSRRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3)							
	Appayyanna Beedi	Cum	1	90	4	0.15	52.65	
	MES School Road	Cum	1	104	4	0.15	62.4	
	Parallel Road to Railway Track							
		Cum	1	10	16	0.15	24.00	
		Cum	1	8	10	0.15	12.00	
		Cum	1	11	4	0.15	6.60	
		Cum	1	13	4	0.15	7.41	
		Cum	1	15	10	0.15	22.5	
	Parallel Road to Railway Track	Cum	1	37	5	0.15	25.53	

Sl No	Description of work	Mesurement					Qty	Rate	Amount
		Unit	No.	L	B	D			
	Basic rate							5102.00	
	Area weightage 6%							306.12	
	Total						213.09	5408.12	1152416.29

- 17 Cement concrete pavement. Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum, coarse and fine aggregate confirming to IS:383-2016, with superplasticiser @ 3lts confirming to IS9103-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour, hire charges of machineries, all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum Pg No.176 Item No.22.6.1

Appayyanna Beedi	Cum	1	90.00	3.90	0.15	52.65			
MES School Road	Cum	1	104	4	0.15	62.4			
Parallel Road to Railway Track									
	Cum	1	10	16.00	0.15	24.00			
	Cum	1	8	10.00	0.15	12.00			
	Cum	1	11.00	4.00	0.15	6.60			
	Cum	1	13	3.8	0.15	7.41			
	Cum	1	15	10	0.15	22.5			
Parallel Road to Railway Track	Cum	1	4.60		0.15	25.53			
Administrative Sanction for Rs. 99.12 Lakhs only									
Basic rate								4916.00	
Area weightage 6%								294.96	
Total							213.09	5210.96	1110403.47

Technical Sanction
Accorded For Rs. 99.12 Lakhs only

Head of A/C P.3722
CER NO. 103 D. 28-10-19

TA
CE (YKK)

is accorded under head P. 3722	Grand Total	8307690.47
Chief Minister, A.A. Nagaraj	DPR Charges (1% of estimated cost)	99000.00
Grant 2018-19	Project management And Consultancy Charges (1% of estimated cost)	99000.00
Registered as CE No	GST Charges (12% of estimated cost)	996922.86
to conditions of contract	KRIDL Charges (4% of estimated cost)	396000.00
No. E.21.Y.NK/MS/25/2019-20	Miscellaneous and rounding	1,386.67
	Total Amount	9900000.00
	RUPEES NINETY NINE LAKHS ONLY	

CERTIFICATE:

- 1) The work spot has been inspected and found to be necessary
- 2) The work spot comes under B.B.M.P
- 3) The provisions made in the estimate are necessary and minimum
- 4) The estimate is based on C.S.R of 2018-2019, Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP